


VENUE Ш

PLAN PREPARED BY:

642 Brooksedge Blvd Westerville, OH 43081 P: 614.942.6042 F: 614.942.6041




Date: 04/17/2015 **Scale:** 1" = 40'

Checked B

**Drawing Number:** 

1/1



VENUE S NOAH

PLAN PREPARED BY:

642 Brooksedge Blvd Westerville, OH 43081 P: 614.942.6042


Date: 04/17/2015

Checked B

**Drawing Number:** 

1/1





BY GRAPHIC PLOTTING ONLY THIS PROPERTY IS LOCATED IN ZONE "X" (AREAS DETERMINED TO BE OUTSIDE OF THE 50B-YEAR FLOOD PLAIN) BY THE FEDERAL EMERGENCY MANAGEMENT AGENCY ON FLOOD INSURANCE RATE MAP, COMMUNITY PANEL NO. 39049C0131K WITH AN EFFECTIVE DATE OF JUNE 17, 2008 IN FRAI COUNTY, OHIO. NO FIELD SURVEYING WAS PERFORMED TO DETERMINE THIS ZONE AND AN ELEVATION CERTIFICATE MAY BE NEEDED TO VERIFY THIS DETERMIN APPLY FOR A VARIANCE FROM THE FEDERAL EMERGENCY MANAGEMENT AGENCY.

THE IDENTITY AND LOCATION OF EXISTING UNDERGROUND UTILITIES LOCATED IN AND AROUND THE CONSTRUCTION AREA HAVE BEEN SHOWN AND LABELED ON THE PLANS BY USING MOPOWATION PROVIDED BY THE RESPECTIVE UTILITY OWNERS. THE CITY OF COLUMBUS ON THE CONSULTING ENGINEER WILL NOT ASSUME RESPONSIBILITY FOR THE ACCURACY OF LOCATION OR DEPTH OF EXISTING UNDERGROUND UTILITIES AS SHOWN ON THE PLAN.

SUPPORT AND PROTECTION OF ALL UTILITIES AND APPURTENANCES SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR, COSTS FOR THE REPAIR AND RESTORATION OF EXISTING UTILITIES DAMAGED BY THE CONTRACTOR SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR. THE CITY OF COLUMBUS UTILITIES WILL ONLY LOCATE AND MARK MAIN LINE FAULTIES. THE CONTRACTOR SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR. THE CITY OF COLUMBUS UTILITIES WILL ONLY LOCATE AND MARK MAIN LINE FAULTIES. THE CONTRACTOR IS RESPONSIBLE FOR LOCATING ALL SERVICE LATERAL AND LINES. COSTS ASSOCIATED WITH THE ABOVE WORK AND RESPONSIBILITIES SHALL BE INCLUDED IN THE PRICE BID FOR VARIOUS TIEMS.

PRIOR TO EXCAVATION, THE CONTRACTOR SHALL GIVE A 48-HOUR NOTICE TO THE OHIO UTILITIES PROTECTION SERVICE (OUPS) BY CALLING (800) 362-2764, A 48-HOUR NOTICE SHALL BE GIVEN TO THE OWNERS OF UNDERGROUND UTILITIES SHOWN ON THE PLANS WHO ARE NOT MEMBERS OF A REGISTERED UNDERGROUND PROTECTION SERVICE.

LISTED BELOW ARE UTILITY COMPANIES THAT HAVE FACILITIES LOCATED WITHIN THE WORK LIMITS OF THIS PROJECT AND SUBSCRIBE TO OURS

ELECTRICITY	TELEPHONE	NATURAL GAS	TELEPHONE
AMERICAN ELECTRIC POWER CO. (AEP) 1 RIVERSIDE PLAZA COLUMBUS, OHIO 43215	800-277-2177	COLUMBIA GAS 200 SOUTH CIVIC CENTER DRIVE COLUMBUS, OHIO 43215	800-344-4077
WATER	TELEPHONE	TELEPHONE	TELEPHONE
CITY OF COLUMBUS, DIVISION OF WATER 910 DUBLIN ROAD, COLUMBUS, OHIO 43215	614-645-6186	AT& T 150 EAST GAY STREET, COLUMBUS, OHIO 43215	800-660-1000
SEWER	TELEPHONE	CABLE	TELEPHONE
CITY OF DUBLIN, DIVISION OF STREETS &UTILITIES 6555 SHIER RING ROAD, DUBLIN, OHIO 43016	614-410-4750	TIME WARNER CABLE 1015 OLENTANGY RIVER ROAD COLUMBUS, OHIO 43227	614-481-5050
TRACH	TELEBUIONE		TEL EDUIANE

100YR FLOOD 500 YEAR FLOOD



1 inch = 40 feet

Utilities Protection SERVICE

800-362-2764 or 8-1-1 www.oups.org

PLAN PREPARED FOR:

CITY OF DUBLIN/ FRANKLIN COUNTY, OHIO PROPOSED CONDITIONS PLAN **EVENT VENUE** NOAHS

Westerville, OH 43081 P: 614.942.6042 F: 614.942.6041

Date: 04/17/2015 Scale: 1" = 40'

Drawn By: Checked By
RLC CAW

15-028-03

Drawing Number 1/1

### PLAN NOTES

1. SEE SITE PLANS FOR ALL EXTERIOR CONCRETE WALK LOCATIONS. 2. ALL TRANSITIONS BETWEEN EXTERIOR WALLS AND INTERIOR PARTITIONS TO BE FRAMED IN COMMON LINE (UNLESS NOTED OTHERWISE), GC TO COORDINATE.

3. ALL INTERIOR PARTITIONS TO BE TYPE "P1" UNLESS OTHERWISE NOTED. GC TO COORDINATE WALL THICKNESSES WITH PLUMBING/STRUCTURAL REQUIREMENTS, ARCHITECT TO BE NOTIFIED OF ANY CHANGE IN WALL THICKNESS DUE TO SUCH

4. ALL DOORS TO HAVE MIN 1'-6" ON PULL SIDE OF DOOR (FROM DOOR EDGE). 5. ALL DOORS WITH BOTH CLOSER AND LATCH TO HAVE MIN 1'-0" (FROM DOOR EDGE) ON PUSH SIDE OF DOOR.

6. PROVIDE 2" STEEL TUBE (CONCEALED WITHIN WALL) AT ALL PARTIAL HEIGHT WALL LOCATIONS FOR RIGIDITY.

7. DIMENSIONS @ EXTERIOR WALL ARE TO EDGE OF MASONRY.

8. DIMENSIONS @ INTERIOR WALL ARE TO FACE OF STUD UNLESS NOTED

9. LEVEL 4 GYPSUM FINISH TYPICAL. LEVEL 5 FINISH SHALL BE PROVIDED IN THE FOLLOWING AREAS: \_\_\_\_

10. USE GREEN BOARD IN WET LOCATIONS.

#### PARTITION TYPES

P1 TYPICAL WALLS: 2x4 WOOD STUDS AT 16" O.C., 5/8" GWB ON ONE SIDE OR BOTH AS REQ'D FOR FINISH.

**P2** 2X6 WALLS: 2x6 WOOD STUDS AT 16" O.C., 5/8" GWB ON ONE SIDE OR BOTH, AS REQ'D FOR FINISH.

P3 BEARING AND SHEAR WALLS: 2x6 WOOD STUDS AT 16" O.C. WITH ONE LAYER 1/2" STRUCTURAL SHEATHING ON ONE SIDE, 5/8" GWB ON ONE SIDE OR BOTH, AS REQ'D FOR FINISH.

P4 EXTERIOR WALLS: 2x6 WOOD STUDS. SEE STRUCTURAL FOR SPACING AND

#### **LEGEND**

AV1 AUDIO/VISUAL CABINET. SEE ROUGH OPENING REQUIREMENTS ON A8.1 FINISH PLANS AND SCHEDULES

AV2 AUDIO/VISUAL FLOOR BOX. CENTERED ON AV1. SEE DETAIL 7/A4.1.

FLOOR DRAIN, SEE PLUMBING. SLOPE CONCRETE AS NECESSARY AROUND DRAIN TO GAIN POSITIVE DRAINAGE. FRZ FREEZER BY OWNER.

FLOOR SINK, SEE PLUMBING. SLOPE TILE IN STORAGE ROOM 114.

ICE ICE MAKER OR ICE BIN BY OWNER.

LADDER ATTIC ACCESS LADDER. SEE 5/A5.2.

NOT IN CONTRACT, EQUIPMENT SHOWN DASHED TO BE PROVIDED BY OWNER, GC TO PROVIDE NECESSARY ELEC/MECH REQUIREMENTS.

REF REFRIGERATOR BY OWNER.

TRELLIS WALL HUNG TRELLIS PROVIDED BY OWNER, INSTALLED BY GC. SEE A/A3.5.

WH WATER HEATER, REF PLUMBING.


FEC RECESSED FIRE EXTINGUISHER CABINET (MOUNT SO THAT FIRE EXTINGUISHER HANDLE IS 54" AFF MAX).

SHELDEN ARCHITECTURE INSPIRED SPACE

Tel. 316.263.4300 Fax. 316. 263.4301 800 E. First, Suite 140 Wichita, Kansas 67202 SHELDENARCHITECTURE.COM

PROJECT NO.	15-00
ISSUE:	DATE:
<u> </u>	
200	-
70	()
04	
<del></del>	
001	+
2 × 50	
2 <	
<del></del>	
0	

FLOOR PLAN





## PLAN NOTES

- IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO PROVIDE ALL ANCHORS AND ENGINEERING NECESSARY TO INSURE A COMPLETE INSTALLATION OF ALL CAST STONE - INSTALL USING MANUF. RECOMMENDED DETAILS
- 2. CONTRACTOR TO SEAL ALL JOINTS IN CAST STONE WITH COMPATIBLE ELASTOMERIC SEALANT COLOR TO MATCH CAST STONE. PROVIDE BACKER ROD AT ALL JOINTS LARGER THAN 1/4" IN WIDTH.




INSPIRED SPACE
Tel. 316.263.4300
Fax. 316. 263.4301
800 E. First, Suite 140
Wichita, Kansas 67202
SHELDENARCHITECTURE.COM

# MATERIALS LEGEND

FACE BRICK	ACME BRICK, "TEXAS HIGHLANDER".
CAP	METAL COPING CAP, DREXEL METALS, SANDSTONE SR 67.
CAST STONE	CONTINENTAL CAST STONE, ST THOMAS TAN #1103.
CEMENT BD	CEMENT BOARD, MODEL TBD.
DOWNSPOUT	SHEEP'S TONGUE DOWNSPOUT NOZZLE THROUGH WALL, MODEL TBD.
NIC	NOT IN CONTRACT, ITEMS NIC TO BE PROVIDED BY OWNER, GC TO PROVIDE NECESSARY ELEC/MECH REQUIREMENTS.
SCUPPER	THROUGH WALL SCUPPER, TYPE TBD. SEE ROOF PLAN FOR SIZE AND LOCATIONS.
SIGNAGE	BUILDING SIGNAGE REQUIRES SEPARATE APPROVALS.

SMOOTH SAWN FIR TRELLIS PROVIDED BY OWNER AND INSTALLED BY GC. SHERWIN WILLIAMS SHAGBARK STAIN #7093

12"X24" PORCELAIN TILES, DAL-TILE DIAMANTE BIANCO PO 32 MATTE.



**ELEVATIONS** 

A2.1

© 2015 Shelden Architecture, Inc.







## PLAN NOTES

- 1. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO PROVIDE ALL ANCHORS AND ENGINEERING NECESSARY TO INSURE A COMPLETE INSTALLATION OF ALL CAST STONE INSTALL USING MANUF. RECOMMENDED DETAILS
- 2. CONTRACTOR TO SEAL ALL JOINTS IN CAST STONE WITH COMPATIBLE ELASTOMERIC SEALANT COLOR TO MATCH CAST STONE. PROVIDE BACKER ROD AT ALL JOINTS LARGER THAN 1/4" IN WIDTH.



INSPIRED SPACE
Tel. 316.263.4300
Fax. 316. 263.4301
800 E. First, Suite 140
Wichita, Kansas 67202
SHELDENARCHITECTURE.COM

# MATERIALS LEGEND

FACE BRICK ACME BRICK, "TEXAS HIGHLANDER".

CAP METAL COPING CAP, DREXEL METALS, SANDSTONE SR 67.

CAST STONE CONTINENTAL CAST STONE, ST THOMAS TAN #1103.

CEMENT BD CEMENT BOARD, MODEL TBD.

DOWNSPOUT SHEEP'S TONGUE DOWNSPOUT NOZZLE THROUGH WALL, MODEL TBD.

NIC NOT IN CONTRACT, ITEMS NIC TO BE PROVIDED BY OWNER, GC TO PROVIDE NECESSARY ELEC/MECH REQUIREMENTS.

SCUPPER THROUGH WALL SCUPPER, TYPE TBD. SEE ROOF PLAN FOR SIZES AND LOCATIONS.

SIGNAGE

BUILDING SIGNAGE REQUIRES SEPARATE APPROVALS.

TILES

12"X24" PORCELAIN TILES, DAL-TILE DIAMANTE BIANCO PO 32 MATTE.

SMOOTH SAWN FIR TRELLIS PROVIDED BY OWNER AND INSTALLED BY GC. SHERWIN WILLIAMS SHAGBARK STAIN #7093

PROJECT NO.	15-00
ISSUE:	DATE:
110	<
	0
- 2	
, 0	
14	7
0	7
<del></del>	*
00	-
<del>}                                    </del>	

VENUE

NOAH'S

A2.2

© 2015 Shelden Architecture, Inc.

**ELEVATIONS**